

# CUSTONER PARTNERSHIP

# Hong Kong International Airport into a Three-Runway System



Wealth Mind Ltd.

## 1. Introduction

The 3RS project is proposed to be located on a new land formation immediately north of HKIA in North Lantau, covering a permanent footprint of approximately 650ha. The project primarily comprises :

1

•New third runway with associated taxiways, aprons and aircraft stands

•New passenger concourse building

•Expansion of the existing Terminal 2 (T2) building

•Related airside and landside works, and associated ancillary and supporting facilities.



![](_page_3_Figure_0.jpeg)

### 2. Timeframe

It is planned that the land formation work would be undertaken from start of late 2015 / early 2016 to mid-2022, noting that the third runway and taxiway sections (which accounts for the majority of the land formation) would be completed by 2020 for closure of the existing north runway and opening of the third runway by 2021. Based on the construction planning, the land formation works have been primarily divided into three main stages. The works for each stage are described below:

**Stage 1** has a T-shaped footprint and consists mainly of the land formation works for the third runway, the associated west taxiways, the western support area and other supporting facilities.

**Stage 2** consists of land formation works for the new third runway concourse and aprons supported by facilities within the east support area.

**Stage 3** is the land formation area at both ends of the existing north runway associated with the new wrap-around taxiways, whereby construction activities are restricted by the need to maintain operation of the existing north runway until completion of the third runway.

| Phase             | Description                                                                                                                                                                                                                                                                                                                                                    | Runway Operational Configuration                                    | Tim           | eframe |
|-------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------|---------------|--------|
| Advanced<br>Works | Diversion of the submarine pipelines and power cables                                                                                                                                                                                                                                                                                                          |                                                                     | 2015<br>2016  | to     |
| Phase 1           | Land formation works will commence<br>before subsequent construction of third<br>runway, new taxiways and the new TRC.<br>Expansion of T2 will also commence. The<br>existing two-runway system remains<br>operational throughout the construction<br>phase.                                                                                                   | Existing Two<br>Runways                                             | 2016<br>2021  | to     |
| Phase 2           | Upon completion of the third runway and<br>associated taxiways, the existing North<br>Runway will be closed for modification<br>works, while construction activities for the<br>TRC and aprons, vehicle tunnels and<br>reconfiguration of T2 are on-going.<br>During this interim period, the South<br>Runway and the new third runway will be<br>operational. | Operation of<br>new North<br>Runway and<br>existing South<br>Runway | 2021<br>2023  | to     |
| Phase 3           | Upon completion of all essential<br>infrastructure and facilities, including part of<br>the TRC and aprons and expanded T2, the<br>airport will operate under the 3RS.<br>Construction of the remaining facilities<br>will continue until completion.                                                                                                          | Operation of<br>Three Runway<br>System                              | 2023<br>after | and    |

### **Appendix 4.2 - Tentative Construction Programme**

| Line | e Name                           | 2015   | i I | 20     | 16       |   | 2017        |        | 1 | 2018                                     | }           | Ì      | 2019 |          |           | 2020             | I         | 202       | 1              |   | 2022 |        | 20    | 23 |
|------|----------------------------------|--------|-----|--------|----------|---|-------------|--------|---|------------------------------------------|-------------|--------|------|----------|-----------|------------------|-----------|-----------|----------------|---|------|--------|-------|----|
|      | Advanced Works                   |        |     |        |          |   | 1           |        |   | 1                                        | 1           |        |      | 1        |           | 11               |           |           |                | 1 |      |        | 1     |    |
| 1    | Aviation Fuel Pipeline Diversion | 100000 |     |        |          |   |             |        | 1 |                                          | 1           | 1      |      | 1        |           |                  |           | 11        | 1              | 1 | 1    |        |       | 1  |
| 2    | Power Cable Diversion            | 2      |     |        |          |   |             | -      |   |                                          | 1           |        | H    | T        |           | П                |           | 11        | 1              |   |      |        |       | 1  |
| 3    | Land Formation                   |        |     | +      |          |   | +           | +      |   | +                                        | 1           |        |      | +        | +         | +                |           |           |                | + | +    |        | +     | +  |
| 4    | Sand Blanket Laying              | i i    | 1   | anara. |          |   | 1.1.1.1.1.1 | www.du |   | i                                        | 1           |        |      |          | 1         |                  |           | 1.1.1.1.1 |                |   | 1    | i      |       | i  |
| 5    | Ground Improvement Works         |        | 5   |        |          |   |             |        |   |                                          |             | 1      |      | 1        |           |                  |           |           |                |   |      |        | 1     | 1  |
| 6    | Construction of Seawall          |        |     | 6      | Yest the |   |             | 10.00  |   |                                          | 1           |        |      |          |           |                  |           | 120.00    |                |   | 1    |        |       |    |
| 7    | Marine Filling                   |        |     |        | 7        |   |             |        |   | an a | (*)*(*      |        |      |          |           |                  |           |           | 1.101          |   |      |        |       |    |
| 8    | Land Filling                     | li i   |     | ì      | 3        |   |             |        |   | * * * *                                  |             |        | i    | î.       | i         | 1 i              |           | i i       | 1227           | í | 1    | i      | i     | i  |
| 9    | Surcharge                        |        |     |        |          | 9 | Selectore   |        |   | a da da da                               | -           |        |      | S        |           |                  |           |           | den en         |   |      |        |       |    |
|      |                                  | li i   |     | j.     |          |   | 1           | i      | i | i                                        | j.          |        | i i  | i        | j.        | i i              |           | 11        | i.             | i | 1    | i. I   | 1     | i. |
| 10   | Third Runway / Taxiway           |        |     |        |          |   |             |        |   |                                          | 2.5         |        | 25   |          | 28        |                  |           |           | 2.5            |   | 8    |        | - 3   |    |
| 11   | Drainage / Utilities             | l i    |     | 1      |          |   | 1           | i      | i | u.                                       | (1) (1) (1) |        |      |          | 4,494.43  | - i              |           | 1 1       | i              | i | 1    |        |       | 1  |
| 12   | Pavement                         |        |     |        |          |   |             |        |   |                                          |             | 2 1911 |      | energe o |           |                  |           |           |                | 1 |      |        |       |    |
| 13   | System & T&C                     |        |     | -      |          | H | -           | -      |   | 1                                        |             |        |      | 13       | alalaha a | e a se a se a se | ala Alala |           |                | - | -    |        | -     | -  |
| 14   | Third Runway Concourse (TRC)     |        |     | +      | H        | H | Ť           | +      | 1 | +                                        | +           |        | +    | 1        | +         | +                |           | H         | +              | + | 1    |        | t     | +  |
| 15   | Piling                           |        | Ť   |        |          |   |             |        |   |                                          |             |        |      | IS       | 212.00    | 10000            | 1.1.1     |           |                |   |      |        |       |    |
| 16   | APM/BHS Sub-structure            |        |     | 1      |          |   | 1           | 1      | 1 | 1                                        | 1           |        |      | 1        | 16        | 1.00.00          | unina     |           |                |   | 1    |        |       |    |
| 17   | Super-structure                  | 1      |     |        |          |   |             |        |   |                                          |             |        |      |          |           | 17               | ere er    | deres de  | and the second |   |      |        |       |    |
| 18   | ABWF, E&M & Airport System       |        |     |        |          |   | I           | 1      | 1 |                                          | 1           |        | 1 1  | 1        | 1         | 13               |           |           |                |   |      | -      |       | 1  |
| 19   | T&C                              | 1 1    |     | 1      |          |   | 1           | 1      | 1 | 1                                        |             |        | 11   | 1        |           | 11               |           | 11        | 1              | 1 | 19   | dere d | weie. |    |
|      |                                  |        |     | 1      |          |   |             |        |   | 1                                        | 1           |        |      |          |           |                  |           |           |                |   | -    | 1      |       |    |

### 3. Environmental Impacts, Suggestion & Adventages

|                    | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Competitor                                                                                                                                                                                                                                                                                                                                                                                                     | Requirment                                     | What WML done                                                                                                                                                                                                                                                                                                                                                                                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Requirment                                                           |
|--------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------|
| Air Quality Impact | Construction dust could be generated from<br>construction activities such as land formation,<br>filling, material handling and hauling during<br>land formation, movement of construction<br>traffic over reclaimed land, and wind erosion<br>from the site after reclamation works. If<br>uncontrolled, the extent of consturction dust<br>impacts resulting from wind erosion and<br>construction vehicle movements on the<br>unpaved reclaimed land could potentially be<br>significant due to the large area involved in<br>the Airport expansion works. There would also<br>be air pollutant emissions from operation of<br>construction plant, vehicles and barges. | <b>Conventional dredging</b><br>This type of conventional land formation has<br>a proven track record for application in<br>Hong Kong.<br>Ground improvement works via dredging<br>and disposal of marine sediment will<br>generate substantial sediment plumes with<br>its associated adverse impacts to water<br>quality and marine ecology, as well as large<br>volumes of waste needing off-site disposal. | Bulldozer<br>Wheel<br>Loader                   | - Coopreated with Engineering<br>Company to submitted the<br>Environmental Protection<br>Construction Methods<br>- Coopreated with Environmental<br>Groups to provide the Key Dust<br>Emission Report to prove that the<br>dust Emission will be increase<br>when using the Conventional<br>Dredging Method for Land-based<br>filling works.                                                    | Non-dredged with Deep Cement Mixing Method (DCM)<br>DCM is proposed whereby cement is injected and mixed into<br>columns of the soft mud below a san capping layer to increase its<br>strength and stiffness, allowing land formation above without the<br>realese of contaminated sediment. This method has been widely<br>used in Japan and Asia. This non-dredge method differs fron the<br>other methods in that it provide in-situ treatment and stabilisation<br>of the marine sediment, which reduces the potential of release of<br>contaminated pore water.<br>During the proposed DCM process that would be carried out as<br>part of the ground improvement works for land formation, cement<br>powder will be transferred from supporting vessels to DCM barges<br>through piping in closed loop, or in a totally enclosed manner.<br>There will be no open stoage of cement on the DCM barges.<br>Therefore, it will be reduce the dust impacts due to cement<br>transfer or storage are anticipated. | - Increase the usage<br>of Excavator & Dump<br>Truck due to the DCM. |
| Noise Impact       | Airbone noise would be generated from<br>construction activities such as land<br>formation,infrastructure works and operation<br>of powered mechanical equipment (PME). In<br>addition to noise from operation of PME,<br>noise would also be generated from traffic,<br>especially heavy vehicles, onsite and along<br>access roads.                                                                                                                                                                                                                                                                                                                                     | NIL                                                                                                                                                                                                                                                                                                                                                                                                            | - Normal<br>Working hour<br>from 0800<br>-1800 | <ul> <li>Machine with T3A Engine</li> <li>Strengthen the filter assy and<br/>add warning light</li> <li>Add automatic detection<br/>technology management system<br/>which can show the emissions<br/>automatly.</li> <li>provide QPME, NRMM &amp;<br/>cetification of all Doosan machine<br/>to AAHK</li> <li>Used Noise enclosure or<br/>acoustic shed to cover stationary<br/>PME</li> </ul> | The construction may potentially generate ground-borne & vibration noise impacts. But the land formation work will be consturcted by DCM which is no rock breaking or tunnel mining works involved in the underground construction. Therefore, no ground-borne & vibration noise impact is anticipated during the construction phase.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | - Extend Working<br>Hour from 0800 -<br>2100                         |

DOOSAN PARTNERSHIP CONFERENCE

| Description                                                                                                                                                                                                                                                                                                            | Competitor                                                                                                                                  | Requirment                                       | What WML done                                                                                                    |                                                                                                                                                                                                                                                                                    | Requirment                                                              |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------|------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------|
| Marine works such as land formation and<br>filing would possibly generate increased<br>level of suspended solids, generation of<br>sediment plume, re-deposition of sediment<br>and subsequent deterioration of water<br>quality which might indirectly cause<br>disturbance impact on marine habitat and<br>wildlife. | Nil                                                                                                                                         | Nil                                              | - Coopreated with<br>Engineering Company to<br>submitted the Environmental<br>Protection Construction<br>Methods | Non-dredged with Deep Cement Mixing Method (DCM)<br>DCM avoids disturbance to the seabed and also avoids the<br>removal of contaminated sediment during land formation and<br>provides an environmentally friendly way of ground<br>improvements at the Contaminated Mud Pit area. | - Increase the usage<br>of Excavator & Dump<br>Truck due to the<br>DCM. |
| Waste management implications during the<br>construction phase will be from generation,<br>handling and disposal of waste. C&D<br>materials would arise from demolition of<br>existing seawalls and generated as excess<br>fill materials and other construction materials                                             | Sloping seawall with Circular Steel<br>Cell Cofferdam<br>This type of seawall will arise the waste<br>from demolition of existing seawalls. | -100 to 150 ton<br>Crawler Crane<br>Wheel Loader | - Provided suggestion to AAHK<br>and Environmental Groups                                                        | Sloping seawall with 2 - 3.5m3 Marble<br>This type of seawall as presenting an environmental advantage<br>from the perspectives of wase minimisation and marine<br>ecological habitat as all of rock armour from existing northern<br>seawall will be reuse.                       | - 50 - 70ton<br>Excavator                                               |

During 2008 – 2014, Airport Authority Hong Kong (AAHK) & Environmental Protection Department (EPD) have organized some focused consultation with industry representatives and commissioned relevant consultants to conduct feasibility studies covering initial land formation engineering evaluation, preliminary engineering feasibility and environmental assessment, preliminary noise impact analysis, preliminary air quality impact analysis.

The Environmental Impacts Assessment Report have performance and identified that only the DCM that we submitted which involves filled land formation of the project while minimizing the environmental impact associated with land formation.

A DCM trial was carried out at the contaminated mud pit area during which extensive water quality and underwater noise monitoring was performed to check for any potential environmental impacts. The monitoring results indicated the the DCM work would not cause any appreciable deterioration of water quality and no leakage of contaminants or cement slurry was detected throughout the trial process. It was also found that the DCM work was relatively quiet compared to other marine construction techniques.

Land Formation Work Sequence and Potential Dust Emission Sources

| Wo | ork Sequence                                                                                                                               | Marine-based or Land-based Works                                                                                             | Potential Dust Emission Sources |
|----|--------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------|---------------------------------|
| 1. | Placement of sand blanket (2 m in thickness) on the seabed                                                                                 | Marine-based                                                                                                                 | No                              |
| 2. | Application of the appropriate non-dredged<br>ground improvement methods to improve the<br>engineering properties of the seabed            | Marine-based                                                                                                                 | No                              |
| 3. | Modification of existing seawall and/or<br>construction of new seawall on the pre-improved<br>foundation                                   | Partly marine-based (during marine sand filling) and<br>partly land-based (during placement of rock fill and<br>rock armour) | No for the marine-based part    |
|    |                                                                                                                                            |                                                                                                                              | Yes for the land-based part     |
| 4. | Marine sand filling up to +2.5 mPD (not including settlement), which is above high water mark                                              | Partly marine-based (during filling below high water mark) and partly land-based (during filling above high water mark)      | No for the marine-based part    |
|    |                                                                                                                                            |                                                                                                                              | Yes for the land-based part     |
| 5. | Land filling (using sand fill or public fill materials)<br>with vibro compaction from + 2.5 mPD to +<br>6.5 mPD (not including settlement) | Land-based                                                                                                                   | Yes                             |
| 6. | Application of surcharge and subsequent remova                                                                                             | ILand-based                                                                                                                  | Yes                             |

**DOOSAN** PARTNERSHIP CONFERENCE

#### Appendix 5.2.15 - Details of Dust Emission Sources for Annual FSP Assessment at Year 2016

#### Third Runway Work Areas

| Works Area                     | Sources                                                                                        |                                  | Parameter                                                        | Remarks                                                                                                                                                  |
|--------------------------------|------------------------------------------------------------------------------------------------|----------------------------------|------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------|
| Third Runway Land<br>Formation | Heavy construction<br>Source ID:<br>For 24hrs activities:                                      | Percentage active area, p        | 0.1 %                                                            | Assume % works area for heavy construction                                                                                                               |
|                                | Q1:                                                                                            | Mitigation efficiency            | 91.7 %                                                           | Water suppression 12 times a day<br>Equation (3-2) in the USEPA's Control of Open Fugitive Dust<br>Sources Final Report                                  |
|                                | Q2:                                                                                            | No. of working days per month, d | 30 days                                                          |                                                                                                                                                          |
|                                | Q3:                                                                                            | No. of working hours per day, h  | 24 hour                                                          |                                                                                                                                                          |
|                                | Q4: 1_03-1, 1_03-2, 1_08A-1, 1_08A-2, 1_08B-1, 1_08B-2, 2_04-1, 2_04-2, 2_06-1, 2_06-2, 2_06-3 | Emission Factor (0.03)           | 0.0807 Mg/hectare/month of activity                              | AP42, Section 13.2.3.3<br>Thompson G. Pace, USEPA. Examination of the Multiplier Used to<br>Estimate PM2.5 Fugitive Dust Emissions from PM10, April 2005 |
|                                |                                                                                                | Emission Rate                    | 2.8559E-09 g/m²/s (unmitigated)<br>2.3704E-10 g/m²/s (mitigated) | =2.69*0.03*1000000/(10000*30*h*60*60)*p/100                                                                                                              |
|                                | Wind Erosion<br>Source ID: (as above)                                                          | Percentage active area, p        | 0.1 %                                                            |                                                                                                                                                          |
|                                |                                                                                                | Emission Factor (0.03)           | 0.0255 Mg/hectare/year                                           | AP42, Table 11.9-4<br>Thompson G. Pace, USEPA. Examination of the Multiplier Used to<br>Estimate PM2.5 Fugitive Dust Emissions from PM10, April 2005     |
|                                |                                                                                                | Emission Rate                    | 7.41717E-11 g/m²/s                                               | =0.85*0.03*1000000/(10000*365*24*60*60)*p/100                                                                                                            |
|                                |                                                                                                |                                  |                                                                  |                                                                                                                                                          |

Appendix 5.2.15 - Details of Dust Emission Sources for Annual FSP Assessment at Year 2017

#### Third Runway Work Areas

| Works Area        | Sources                                                                                                                                                                                                               | 1                                | Parameter                                                                                    | Bemarks                                                                                                                                                  |
|-------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------|----------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------|
| Third Bunway Land | Heavy construction                                                                                                                                                                                                    | Percentage active area, p        | 1.4 %                                                                                        | Temarka                                                                                                                                                  |
| Formation         | Source ID:<br>For 24hrs activities:                                                                                                                                                                                   | r oroontago aotro aloa, p        |                                                                                              | Assume % works area for heavy construction                                                                                                               |
|                   | 01: 1_01, 1_03-1, 1_03-2, 1_04, 1_07-1, 1_07-2, 1_08A-1, 1_08A-2, 1_08B-<br>1, 1_08B-2, 1_09-1, 1_09-2, 2_03B, 2_04-1, 2_04-2, 2_05B-1, 2_05B-2, 2_06-1, 2_06-2, 2_06-3, 2_07B, 2_08, 2_09-1, 2_09-2                  | Mitigation efficiency            | 91.7 %                                                                                       | Water suppression 12 times a day<br>Equation (3-2) in the USEPA's Control of Open Fugitive Dust<br>Sources Final Report                                  |
|                   | Q2: 1_01, 1_02-1, 1_02-2, 1_03-1, 1_03-2, 1_04, 1_07-1, 1_07-2, 1_08A-1, 1_08A-2, 1_08B-1, 1_08B-2, 1_09-1, 1_09-2, 2_03B, 2_05B-1, 2_05B-2, 2_07A-1, 2_07A-2, 2_07B, 2_08, 2_09-1, 2_09-2, 3_01A-1, 3_01A-2, 3_01A-3 | No. of working days per month, d | 30 days                                                                                      |                                                                                                                                                          |
|                   | 03: 1_01, 1_02-1, 1_02-2, 1_03-1, 1_03-2, 1_04, 1_05, 1_07-1, 1_07-2,<br>1_08A-1, 1_08A-2, 1_08B-1, 1_08B-2, 2_03B, 2_05B-1, 2_05B-2, 2_07A-1,<br>2_07A-2, 2_07B, 2_08, 3_01A-1, 3_01A-2, 3_01A-3                     | No. of working hours per day, h  | 24 hour                                                                                      |                                                                                                                                                          |
|                   | 04: 1_01, 1_02-1, 1_02-2, 1_03-1, 1_03-2, 1_04, 1_05, 1_07-1, 1_07-2,<br>1_08A-1, 1_08A-2, 2_03B, 2_05A, 2_05B-1, 2_05B-2, 2_07A-1, 2_07A-2,<br>2_07B, 2_08                                                           | Emission Factor (0.03)           | 0.0807 Mg/hectare/month of activity                                                          | AP42, Section 13.2.3.3<br>Thompson G. Pace, USEPA. Examination of the Multiplier Used to<br>Estimate PM2.5 Fugitive Dust Emissions from PM10, April 2005 |
|                   |                                                                                                                                                                                                                       | Emission Rate                    | 4.45002E-08 g/m <sup>2</sup> /s (unmitigated)<br>3.69352E-09 g/m <sup>2</sup> /s (mitigated) | =2.69*0.03*1000000/(10000*30*h*60*60)*p/100                                                                                                              |
|                   | For night-time activities:                                                                                                                                                                                            | Percentage active area, p        | 1.4 %                                                                                        |                                                                                                                                                          |
|                   | Q1:                                                                                                                                                                                                                   | Mitigation efficiency            | 91.7 %                                                                                       |                                                                                                                                                          |
|                   | Q2: 2_04-1, 2_04-2, 2_06-1, 2_06-2, 2_06-3                                                                                                                                                                            | No. of working days per month, d | 30 days                                                                                      |                                                                                                                                                          |
|                   | Q3: 1_09-1, 1_09-2, 2_04-1, 2_04-2, 2_06-1, 2_06-2, 2_06-3, 2_09-1, 2_09-2                                                                                                                                            | No. of working hours per day, h  | 12 (night) hour                                                                              |                                                                                                                                                          |
|                   | Q4: 1_09-1, 1_09-2, 2_04-1, 2_04-2, 2_06-1, 2_06-2, 2_06-3, 2_09-1, 2_09-<br>2, 3_02A-1, 3_02A-2, 3_02A-3                                                                                                             | Emission Factor (0.03)           | 0.0807 Mg/hectare/month of activity                                                          | AP42, Section 13.2.3.3<br>Thompson G. Pace, USEPA. Examination of the Multiplier Used to<br>Estimate PM2.5 Fugitive Dust Emissions from PM10, April 2005 |
|                   |                                                                                                                                                                                                                       | Emission Rate                    | 8.90004E-08 g/m²/s (unmitigated)<br>7.38703E-09 g/m²/s (mitigated)                           | =2.69*0.03*1000000/(10000*30*h*60*60)*p/100                                                                                                              |
|                   | Wind Erosion<br>Source ID: (as above)                                                                                                                                                                                 | Percentage active area, p        | 1.4 %                                                                                        |                                                                                                                                                          |
|                   |                                                                                                                                                                                                                       | Emission Factor (0.03)           | 0.0255 Mg/hectare/year                                                                       | AP42, Table 11.9-4<br>Thompson G. Pace, USEPA. Examination of the Multiplier Used to<br>Estimate PM2.5 Fugitive Dust Emissions from PM10, April 2005     |
|                   |                                                                                                                                                                                                                       | Emission Rate                    | 1.15573E-09 g/m²/s                                                                           | =0.85*0.03*1000000/(10000*365*24*60*60)*p/100                                                                                                            |
|                   |                                                                                                                                                                                                                       |                                  |                                                                                              |                                                                                                                                                          |

![](_page_13_Figure_0.jpeg)

![](_page_14_Figure_0.jpeg)

**DOOSAN** PARTNERSHIP CONFERENCE

![](_page_15_Figure_0.jpeg)

![](_page_16_Figure_0.jpeg)

### 5. Overview

#### Our Works :

•Airport Authority Hong Kong (AAHK) & Environmental Protection Department (EPD) have organized some focused consultation with industry representatives

- •WML provides a lot of environmental concept and suggestion to AAHK & EPD to increase the environmental standards, in order to reduce the demand of competitor thus increasing the supply of our company .
- •We have cooperated with Engineering Company to submit the Environmental Protection Construction Methods DCM, and have cooperated with Green Group to provide the Key Dust Emission Report to prove that the dust Emission will be increase when using the Conventional Dredging Method for Land-based filling works

•Airport Authority Hong Kong (AAHK) & Environmental Protection Department (EPD) have commissioned relevant consultants to conduct feasibility studies covering initial land formation engineering evaluation, impact analysis and perforance the Environmental Impacts Assessment and it identified that only DCM which minimize the environmental impact.

![](_page_17_Picture_6.jpeg)

#### **Our Target :**

It is planned that the land formation project would be started from end of 2015 to early of 2016. The CHEC reclamation project that we're working, there was generate around total 60units ADT (around 15units ADT for 10000m3) therefore we evaluated that the 3RS project will be generate around 300 units ADT & 200 units Excavator. So our target would be 150 units ADT & 100 units Excavator on this 3RS project.

![](_page_18_Figure_2.jpeg)

18

#### Our Needs :

- 1. All machine with minimum T3A Engine
- 2. Strengthen the filter assy's and add warning light
- 3. Add automatic detection technology management system which can show the emissions automatically
- 4. Strengthen the noise enclosure of all machine
- 5. Spare Part Consignment around 10% at machine value
- 6. At lease 6 months preparation of machine
- 7. Doosan engineer on-time checking
- 8. Review dealer price timely
- 9. DC pricing
- 10. Strategies / Suggestion, due to the big demand of machine, all competitors will provide a very attractive pricing or program, such as buy back or rental.
- 11. Letter of indemnity, CAT have provide an official letter to our customer to promise that 25 units can be produce on 1 day, if fully occupy.

![](_page_19_Picture_13.jpeg)

# END